TAMIL NADU TRANSMISSION CORPORATION LIMITED
(A Subsidiary of TNEB Limited)

From
Er.V.Pulamadan, B.E.,
Chief Engineer/Grid Operation,
TNSLDC, TANTRANSCO,
3rd Floor, TANTRANSCO Building,
No.144, Anna Salai,
Chennai-600 002

To
The Member Secretary,
Southern Regional Power Committee,
29, Race Course Cross Road, Bengaluru - 560 009

Lr. No. CE/GO / SE/LD&GO / EE/AEE1/ATC / F. 4/ D. 371 / 2026, Dt. 29 .10.2026

Sir,

Sub: Inclusion of an agenda item in the 244th OCC meeting: shutdown of the 230 kV D/c S R Pudur-Sankaneri-Kudankulam feeder (Locations 307 to 309) for NHAI vertical clearance improvement work on NH47 - Reg.

Ref: Outage coordination of the SRPC Secretariat on the TANTRANSCO planned outage request (Category C) for 23-Nov-2026 to 24-Nov-2026.

****

1. With reference to the above, TANTRANSCO has requested a planned shutdown of the 230 kV DC S R Pudur-Sankaneri-Kudankulam feeder from 08:00 hrs on 23.11.2026 to 18:00 hrs on 24.11.2026 (two days).
    a. The shutdown is required to improve the vertical clearance of the line over NH 47 at CH 16+376 km, between Locations 307 and 308.
    b. The work is being carried out on a Deposit Contribution Work (DCW) basis for NHAI, Nagercoil.

2. The scope of work comprises:
    - Dismantling two existing G+0 type towers at Locations 307 and 309 and one KSO+0 type tower at Location 308, and releasing the associated conductors and insulators.
    - Erecting two new NMD+9m towers at Locations 307A and 308, and two new KSO+3m towers at Locations 307 and 309.
    - Stringing Zebra conductor.
3. Further, it is submitted that during outage coordination, the request was not approved. TANTRANSCO was advised to place the matter as an agenda item in the upcoming 244th OCC meeting, since the work involves NHAI-related diversion work. It was also noted that:
    - FTC is required after completion of the work.
    - N-1 is not available for S R Pudur during the shutdown, and TANTRANSCO is to carry out load management in case of any contingency.
    - In future, any planned NHAI diversion or construction-related work shall be routed through the main OCC forum.
4. In view of the above, it is requested that the following item be included in the agenda of the 244th OCC meeting:

    "Shutdown of the 230 kV DC S R Pudur-Sankaneri-Kudankulam feeder from 23-Nov-2026 08:00 hrs to 24-Nov-2026 18:00 hrs for improving the vertical clearance on NH47 at CH 16+376 km (NHAI, Nagercoil) - TANTRANSCO."

    Considering the importance of the work, the subject LC proposal may please be included in the agenda of the 244th OCC meeting and that the SRPC Forum kindly consider the following:

    a. To deliberate and approve the shutdown for the period requested.

b. To note that TANTRANSCO will carry out load management at S R Pudur during any contingency, as N-1 is not available.

c. To note that FTC will be carried out on completion of the work.

d. To note Note that planned NHAI diversion or construction-related works will henceforth be routed through the main OCC forum.

29/10/25

Chief Engineer/Grid Operation

Copy submitted to:

1. The Managing Director/TANTRANSCO
2. The Director/Operation

Copy to :

1) The Chief Engineer/ TP & SO/ Madurai
2) The SE/O/Tirunelvelli
3) The EE/Sub-LDC/Madurai