पावर ग्रिड कॉर्पोरेशन ऑफ इंडिया लिमिटेड
(भारत सरकार का उद्यम)
POWER GRID CORPORATION OF INDIA LIMITED
(A Government of India Enterprise)

Ref SRTS-II/AM-RTAMC/2026-27/ 479 Date: 03rd Nov 2026

The Member Secretary
Southern Regional Powder Committee
No.29, Race Course Road,
Benguluru-560009

Dear Sir,

Sub: Request for agenda for 243rd OCC meeting: Approval of Shutdown of 400/230 kV, 315 MVA ICT-2 at Udumalpet Substation for ICT Augmentation Works-reg

As per the CTU Office Memorandum dated 08.05.2025, approval has been accorded for the augmentation/replacement of the existing 400/230 kV, 315 MVA ICT-2 at Udumalpet Substation with new 500 MVA ICT, with an implementation timeframe of 21 months.

The new 500 MVA ICT is presently under final factory testing and is expected to be dispatched during the second week of November 2026 and received at site by mid-December 2026.

The augmentation work involves:

- Strengthening of the existing ICT foundation.
- Construction of a new foundation for the radiator bank.
- Dismantling and removal of the existing 315 MVA ICT-2.
- Erection, testing, and commissioning of the new 500 MVA ICT.
- Casting of new foundations for 220KV Isolators(02sets), 220KV CT(01Set), LA(01Set).

Considering the above activities and the time required for safe execution of the replacement work, it is proposed to avail the shutdown of the existing 400/230 kV, 315 MVA ICT-2 at Udumalpet Substation from 15.12.2026 to 14.04.2027 (04 months).

In view of the above, SRPC OCC is kindly requested to consider and approve the continuous shutdown of 315 MVA ICT-2 at Udumalpet Substation from 15.12.2026 to 14.04.2027 to facilitate the ICT augmentation works and ensure timely commissioning of the new 500 MVA ICT.

Thanking You.

Yours faithfully,

3/11/26

(S Suresh)
Chief General Manager
AM, SR-2, Bengaluru.